## PLANS OF PROPOSED

P.P.C.C. BRIDGE OVER



DESIGN	DATA
DESIGN	DATA

**SPECIFICATIONS** 

AASHTO LRFD Bridge Design Specifications, First Edition, 1994 plus 1996/97 Interims

VEHICULAR LIVE LOADING

Modified AASHTO HSS-25 Truck 2. AASHTO LRFD "HL-93" Loading

STRUCTURAL CONCRETE

CSA A23.1, Exposure Class C-1 Air content category 1

1. PRECAST PRESTRESSED CONCRETE CHANNEL GIRDERS f'c = 45 MPa at 28 days f'ci = 35 MPa at time of de-stressing

2. PRECAST PANELS - f'c = 35 MPa

REINFORCING STEEL

PRECAST PRESTRESSED CONCRETE CHANNEL GIRDERS - CAN/CSA-G30.18-M92 Grade 400W black (i.e no epoxy coating) 2. PRECAST PANELS - CAN/CSA-G30.18-M92 Grade 400W black (i.e no epoxy coating)

STRUCTURAL STEEL

All Structural Steel shall conform to CAN/CSA G40.21-M92 Grade 300W
 HSS Tubing for Bridge Rail shall confrom to CAN/CSA- G40.21-M92 Grade 350W

MAXIMUM FACTORED LOAD

END PILE BENTS

INTERMEDIATE PILE BENTS

HYDRAULIC DESIGN DATA

DESIGN DISCHARGE

### SURVEY CONTROL

HORIZONTAL DATUM: VERTICAL DATUM: GRS 1980 ELLIPSOID: GEOID (HT2.0): \_\_\_\_\_ ZONE \_\_\_ SCALE FACTOR:

SITE CONTROL POINT DATA

CONTROL POINT \*\_\_\_\_\_

CONTROL POINT \*\_\_\_\_\_

EASTING: ELEVATION: NORTHING:

CONTROL POINT \*\_\_\_\_\_

ELEVATION:

LENGTH

24 368 OUT TO OUT OF ABUTMENT PRECAST BACKWALL PANELS

SUPERSTRUCTURE

TWO SIMPLY SUPPORTED SPAN OF PRECAST PRESTRESSED CONCRETE CHANNEL GIRDERS WITH ASPHALT OVERLAY

SUBSTRUCTURE

TWO PRECAST CONCRETE ABUTMENTS AND ONE INTERMEDIATE BENT WITH STEEL H-PILES

ROADWAY WIDTH

LOCATION

12 000 OUT TO OUT OF GIRDERS



# PLACE LOCATION MAP HERE

RGE. -

LOCATION MAP Not to Scale

## MANITOBA INFRASTRUCTURE

WATER MANAGEMENT AND STRUCTURES

EXECUTIVE DIRECTOR OF STRUCTURES DATE \_\_\_\_\_\_\_\_\_

ENVIRONMENTAL APPROVALS
MANITOBA ENVIRONMENT ACT LICENCE
DATE :
FILE *:
FISHERIES AND OCEANS CANADA - AUTHORIZATION OR REVIEW
DATE :
FILE *:
TRANSPORT CANADA - NAVIGATION ACT
DATE :
FILE *:
MANITOBA INFRASTRUCTURE ENVIRONMENTAL APPROVAL
DATE :
FILE *:
ENVIRONMENTAL REVIEW COMPLETED
DATE :
 COMPLETED BY :

SHEET LEGEND

COVER SHEET

BORING LOGS

GENERAL ELEVATION

ASSEMBLY DETAILS ASSEMBLY DETAILS

STEEL PILE CAP DETAILS

STEEL PILE CAP DETAILS

10. RAILING LAYOUT AND DETAILS

RAILING DETAILS 12. RAILPOST DETAILS

P1. PRECAST PANEL DETAILS

P2. PRECAST PANEL DETAILS

BEARING AND ERECTION DETAILS

SITE AND EROSION CONTROL DETAILS

G1. PRECAST PRESTRESSED CHANNEL GIRDER DETAILS

G2. PRECAST PRESTRESSED CHANNEL GIRDER DETAILS

G3. PRECAST PRESTRESSED CHANNEL GIRDER DETAILS G4. PRECAST PRESTRESSED CHANNEL GIRDER DETAILS

G5. PRECAST PRESTRESSED CHANNEL GIRDER DETAILS

ALL DIMENSIONS ARE IN MILLIMETRES (mm) AND ALL ELEVATIONS AND STATIONS ARE IN METRES (m) UNLESS SHOWN OTHERWISE.

DATE:

SITE No.

SHEET No. 1


CHECKED BY:

PRESTRESSING STRAND 20-13 Ø low relaxation strands, fpu = 1860 MPa PILE LOADING

FACTORED BEARING RESISTANCE


EASTING:

RELEASED FOR CONSTRUCTION BY



TOTAL LENGTH OF PILES (m) = 0

BILL OF PILE TIPS						
LOCATION	DESCRIPTION	No. OF PILES				
SU.1 & SU.3	Hard-Bite Point HP-77750-B for HP310 x 110 (Abutments)	14				
SU.2	Hard-Bite Point HP-77750-B for HP310 x 110 (Intermediate bent)	9				



## DETAIL OF STEEL HP PILE SPLICE

#### NO ILS.


<u>re: Welding</u>

- 1. Low hydrogen \*E70 series electrodes shall be used.
- 2. The minimum root pass shall be 6 mm.
- 3. Preparation for welding requires 13 mm bevel for HP 250 piles
- and 14 mm bevel for HP 310 piles.
- 4. Weld both flanges and web as shown. The inside bevelling and welds to be completed first.

Not To Scale

5. Before undertaking the back welds, the weld preparation shall be carried out with a carbon Arc-Air gouger.

#### ∗E48018 equivalent metric electrode





#### NOTES:


- 1. Edges of HP Steel pile tip to be ground on 45° bevel for 10 mm.
- 2. Low hydrogen \*E70 series electrodes shall be used.3. The minimum root pass shall be 6 mm.
- ·


∗E48018 equivalent metric electrode


		REVIS	SIONS		GENERAL ELEVATION					
				-	OLNEINAL					
DATE	BY	D	ESCRIPTION				OR CONSTRUCTION			
DES	SIGN	SEAL	RECORD SEAL		anitoba 📆	BY:				
				W	Infrastructure ater Management and Structures					
			NGINEERS	DECION	BY:B.A.N	EXECUTIVE DIRECTO	R OF STRUCTURES DATE			
	ELECTRONIC SEAL			DESIGN	CHECKED:	SCALE: 1:75	SHEET No1			
		HE	KL	DETAILS	BY:K.P		SHEET NO			
			DETAILS	CHECKED:	_ <u>or as shown</u> _	SITE No.				
















MARK No.	No.	DESCRIPTION	CORROSION PROTECTION	SIZE	LENGTH	REMARKS	COMPONENT MASS	MASS PER UNIT	TOTAL MASS
P1	2	Steel plate	Hot dip galvanized		<del></del>	1	<del>                                     </del>	Ol411	1934.48
		Each unit to be fabricated from:				•	<del>                                     </del>	<del>  '</del>	
<del></del>		1 - Steel plate		PL 32x550	7 000	See detail for Abutment	967.120	967.120	<del>                                     </del>
<del></del>		10 - Nelson Type NBL, no thread studs		10 dia.	19	Part No. 101-063-167	0.012		
								967.240	
P1a	2	Steel plate	Hot dip galvanized	<u> </u>	<u> </u>		<del></del>	<del></del>	1934.4
		Each unit to be fabricated from:						·	
		1 - Steel plate		PL 32x550	7 000	See detail for Abutment	967.120		
		10 - Nelson Type NBL, no thread studs		10 dia.	19	Part No. 101-063-167	0.012	0.120 967.240	
							<u> </u>	901.270	
P2	2	Steel plate	Hot dip galvanized						1658.4
		Each unit to be fabricated from:		[			'		
		1 - Steel plate		PL 32x500	6 600	See detail for Intermediate Bent	828.960		
	'	20 - Nelson Type NBL, no thread studs		10 dia.	19	Part No. 101-063-167	0.012		
<del></del>	<del></del>			<u> </u>	<u> </u>		<del></del>	829.200	<del></del>
P3	4		Hot dip galvanized	C310x45	14 000	See detail for Abutment		625.800	
P4	2	Steel channel	Hot dip galvanized	C310x45	13 200	See detail for Intermediate Bent		590.040	1180.0
R30	100	A 325 bolt assembly	Hot dip galvanized	16 dia.	89	Steel plate to channels	<del>                                     </del>	0.245	5 24.5
R32		A325 bolt assembly	Hot dip galvanized		76	Steel plate to channels C'bore holes	<del></del>	0.225	
R35		A325 bolt assembly	Hot dip galvanized		64	Channels to piles	<del>                                     </del>	0.461	127.2
R36	52	A325 bolt assembly	Hot dip galvanized		64	Angles Mk. "S1" to piles & bracket Mk. "S2" to cap		0.205	10.6
S1	22	Angle	Hot dip galvanized	L 152x152x13	250	As detailed	<del> </del> '	7.250	159.5
S2		Bracket	Hot dip galvanized			As detailed	<del>                                     </del>	11.226	
S3		Plate	Hot dip galvanized		<del>                                     </del>	As detailed	<del>                                     </del>	3.223	
S4		Filler plate	Hot dip galvanized		<del>                                     </del>	As detailed	<del>                                     </del>	1.413	
S5		Filler plate	Hot dip galvanized		<del>                                     </del>	As detailed	<del>                                     </del>	0.707	
A1		Structural plate w asher	Hot dip galvanized		150	As detailed - One to threaded rod Mk. "TR2"	<del>                                     </del>	1.766	
A2		Structural plate w asher	Hot dip galvanized			As detailed - One to bolt Mk. "R34"	<del>                                     </del>	0.636	
TR1	40	Threaded rods c/w two hex. nuts	Hot dip galvanized			Girder to steel cap plate	<del>                                     </del>	0.940	
TR3	32	Threaded rods c/w two hex. nuts	Hot dip galvanized		0	Steel plates Mk. "S3" to precast panels	<u> </u>	0.660	
	152	Hardened bevel w asher	Hot dip galvanized	for 16 dia. bolts	•	One to bolts Mk. "R30" & "R32"	<del> </del>	0.110	16.7
<del></del>		Standard flat washer	Hot dip galvanized		1	One to threaded rod Mk. "TR2"	<del>                                     </del>	0.010	
<del></del>		Standard flat washer	Hot dip galvanized		<del>                                     </del>	One to "TR1", tw o to "TR3"	<del>                                     </del>	0.020	
<del></del>		Structural lock w asher	Hot dip galvanized		<del>                                     </del>	One to threaded rod Mk. "TR2"	<del>                                     </del>	0.010	
<del></del>		Structural lock w asher	Hot dip galvanized	for 19 dia. rod	<del>                                     </del>	One to "TR1" & "TR3"	<del>                                     </del>	0.020	
<del></del>		F436 Hardened washer	Hot dip galvanized	for 22 dia. bolts	<del>                                     </del>	One to bolt Mk. "R35"	<del>                                     </del>	0.032	
		F436 Hardened washer	Hot dip galvanized	for 16 dia. bolts		One to bolt Mk. "R36"		0.014	
R1	144	A325 bolt assembly	Hot dip galvanized	22 dia.	76	R.C. girder connection	<del>                                     </del>	0.499	71.8
W1		Structural flat w asher	Hot dip galvanized	for 22 dia. bolts	10	One to bolt Mk. "R1"	<del> </del>	0.499	
		Pair Nord-Lock lock w ashers	Flot dip gaivanies	for 22 dia. bolts	<u></u>	One pair to bolt Mk. "R1"	<del></del>	0.030	
214			i i i i i i i i i i i i i i i i i i i			-		2.224	16
SH1		Shim plate	Hot dip galvanized			As detailed - use as required	<u> </u>	0.231	
SH2	72	Shim plate	Hot dip galvanized	PL 5x80	180	As detailed - use as required	<del> </del> '	0.463	33.
,	<u> </u>	<u></u>	<u> </u>	<u> </u>	·		<u> </u>	ASS (kg) =	1 - 25.1

- NOTES:

  1. All material noted in the above Bill shall be hot dip galvanized after fabrication in accordance with CSA G164 for a minimum net retention of 610 g/m² unless otherwise stated in the
- specified material ASTM standards. The fabricator and galvanizer shall safeguard against embrittlement using recommended practices from applicable standards.
- 2. Seal all welds prior to galvanizing.
- 3. Apply Galvaloy to all field welds and areas where galvanizing has been damaged.
- 4. All bolts and threaded rod in the above Bill shall be Imperial thread.

	REVIS	SIONS	-	STEEL PILE CAP DETAILS					
DATE BY	D	ESCRIPTION				R CONSTRUCTION			
	DESIGN SEAL RECORD SEAL			Infrastructure ater Management and Structures	BY:				
	PLACE ENGINEERS ELECTRONIC SEAL HERE		DESIGN	BY:	EXECUTIVE DIRECTOR	R OF STRUCTURES DATE			
			DESIGN	CHECKED:	SCALE:	Super No. 9			
			DETAIL	BY: K.P	1:5	SHEET No 9			
			DETAILS	CHECKED:	_ or as shown	SITE No			







#### NOTES:


Re: Girder Erection Operations Behind Abutment Ballast Walls


- Surcharge loading on the backfill resulting from girder erection operations shall be minimized near the precast concrete ballast walls and wingwalls.
- Where possible, girder erection equipment shall be positioned such that there are no surcharge loads behind the back face of the precast panels within a distance equal to the depth of backfill to the bottom of the panels at the time of girder erection.
- 3. Should the Contractor propose to encroach on this zone, the following requirements must be satisfied:
- Submit a girder erection procedure for approval outlining type, configuration, weights and locations of equipment including expected tipping forces on crane outriggers, etc.
   Perform all precautionary measures outlined by the Department as a result of that submission.
   All surcharge loads encroaching in this zone must be distributed over an area not less than 2.0 m².


	REVIS	SIONS		BEARING AND ERE	CTION DET	ΓAILS
			- - - -			
			<u>-</u>		<del>i</del>	
DATE BY		ESCRIPTION			RELEASED FO BY:	R CONSTRUCTION
DESIGN	SEAL	RECORD SEAL		anitoba 📆		
		NONEEDS	w	Infrastructure Water Management and Structures		- — — — — — —
	PLACE ENGINEERS ELECTRONIC SEAL HERE		DECIGN	BY:B.A.N	EXECUTIVE DIRECTOR	R OF STRUCTURES DATE
-			DESIGN	CHECKED:	SCALE:	SHEET No10
		DETAILS	BY: K.P	<u>1: 75</u>	SHEET NO	
				CHECKED.	or as shown	SITE No I I
















The girder fabricator shall be responsible for the design, supply and installation of adequate lifting devices c/w 50 deep pockets (cut off min. 25 mm below top surface and grout after installation).


2 Debonded strands / 3 500 each end

END VIEW


Typical layout of 20 - 13 Ø Low Relaxation straight strands









	REVISIONS				T PRF	STRESSED	CHANNEL O	SIRDER DETAILS
						STRESSED	OTI/WINEL C	DINDER DETAILS
DATE	BY	D	ESCRIPTION				RELEASED I	FOR CONSTRUCTION
DES	SIGN :	SEAL	RECORD SEAL	<b>1</b> Ma	<b>unito</b> l	ba 📆	BY:	
	PLACE ENGINEERS ELECTRONIC SEAL HERE			Infrastructure Water Management and Structures				
			DEGLON	BY:	B.A.N	EXECUTIVE DIREC	TOR OF STRUCTURES DATE	
			DESIGN	CHECKED:		SCALE:	SHEET No. G5	
				DETAILS	BY:	K.P		SHEET NO
				INCIAILS			1	








		REIN CAST PA	NFORC	ING			
MARK	TYPE	PIN DIAMETER	LENGTH	PANEL TYPE	No. of PANELS	No. of BARS PER PANEL	TOTAL No. of BARS PER PANEL TYPE
1501_ <b>N</b> 1	STR		6 900	N1	2	6	12
1502_ <b>N</b> 1	STR		600	N1	2	24	48
1501_ <b>N</b> 1a	STR		6 900	N1a	2	6	12
1502_ <b>N</b> 1a	STR		600	N1a	2	24	48
1501_ <b>N</b> 2	STR		6 900	N2	4	10	40
1502 <b>_N</b> 2	STR		1 200	N2	4	24	96
1501_ <b>N</b> 4	STR		4 900	N4	2	16	32
1502 <b>_N</b> 4	STR		1 900	N4	2	17	34
1501_ <b>N</b> 4a	STR		4 900	N4a	2	16	32
1502 <b>_N</b> 4a	STR		1 900	N4a	2	17	34

Total mass of reinforcing steel 1659.80 kg								
Panel Type         N1         N1a         N2         N3         N4         N4								
Area m²/panel	4.90	4.90	9.10	-	10.00	10.00		
Total area of precast Panels 96.00								

#### NOTES:

- 1. All dimensions given in bending diagram are out to out, except radii and extensions on 90°, 135° & 180° hooks. Extensions on 90°, 135° & 180° hooks are the "A" of "G" dimensions for standard 90°, 135° & 180° hooks referenced from the RSIC "Manual of Standard Practice". Radii are inside dimensions. All reinforcing steel bends and hooks shall conform to Clause 6.6.2 of C.S.A. A23.1-04, unless noted otherwise in the BILL OF REINFORCING STEEL.
- 2. All reinforcing steel shall be deformed steel, unless noted otherwise in the BILL OF REINFORCING STEEL.
- 3. All reinforcing steel shall conform to CSA G30.18-M92 "Billet Steel Bars for Concrete Reinforcement" Grade 400W, unless noted otherwise in the BILL OF REINFORCING STEEL.
- 4. Like bars shall be bundled, securely tied and identified as to Mark and Site No. by appropriate means. All other items to be identified in a similar fashion.
- 5. All bars shall be bent in accordance with the following detail:



#### BILL OF MISCELLANEOUS METAL for PRECAST PANELS Site No. CORROSION DESCRIPTION SIZE LENGTH REMARKS PROTECTION Q5 4 Insert units Hot dip galvanized Each unit is fabricated from: PL 10 x 150 Nelson headed concrete anchors, Type H4L, 2 - Studs Mk. "A1" 13 dia. Part No. 101-053-002 - As detailed Nelson deformed bar anchors, Type D2L, 3 - Bars Mk. "A2" 10 dia. Part No. 101-064-537 - As detailed Grade DH or 2H heavy hex. nut, for 19 dia. bolt 2 - Heavy hex. nuts c/w metal or plastic sleeve

#### NOTES:


1. All material noted in the above Bill shall be hot dip galvanized after fabrication in accordance with CSA G164 for a minimum net retention of 610 g/m2 unless otherwise stated in the specified material ASTM standards. The fabricator and galvanizer shall safeguard against embrittlement using recommended practices from applicable standards.

19 dia.

- 2. Seal all welds prior to galvanizing.
- 3. All structural steel to be CSA G40.21 Grade 300W.

R34 8 A325 bolt c/w F436 hardened washer

4. All bolts and inserts in the above Bill shall be Imperial thread.



### NOTES:

- 1. For location of DETAIL "A" see sheet No. P1.
- 2. Precast panel concrete strength: f'c = 35 MPa.

REVI	SIONS	PRECAST PANEL DETAILS					
20//ISSUED FOR	CONSTRUCTION						
DATE BY D	ESCRIPTION				R CONSTRUCTION		
DESIGN SEAL	RECORD SEAL		anitoba 📆	BY:			
		W	Infrastructure ater Management and Structures				
PLACE E	NGINEERS	DESIGN	BY:B.A.N./	EXECUTIVE DIRECTOR	R OF STRUCTURES DATE		
ELECTRO	PLACE ENGINEERS ELECTRONIC SEAL HERE		CHECKED:	SCALE:	SHEET No <u>P2</u>		
	. —		BY:	- — — <del>1 : 2</del> — —	SHEET NO		
		DETAILS	CHECKED:	_ <u>or as shown</u>	SITE No		