

# PLANS OF PROPOSED P.P.C.C. BRIDGE OVER ON

**LENGTH** 36 384 OUT TO OUT OF ABUTMENT PRECAST BACKWALL PANELS

**SUPERSTRUCTURE** THREE SIMPLY SUPPORTED SPAN OF PRECAST PRESTRESSED CONCRETE CHANNEL GIRDERS WITH ASPHALT OVERLAY

**SUBSTRUCTURE** TWO PRECAST CONCRETE ABUTMENTS AND TWO INTERMEDIATE BENTS WITH STEEL H-PILES

**ROADWAY WIDTH** 9 600 OUT TO OUT OF GIRDERS

**LOCATION** IN R.M. OF

## SHEET LEGEND

1. COVER SHEET
2. GENERAL ELEVATION
3. BORING LOGS
4. SITE AND EROSION CONTROL DETAILS
5. ASSEMBLY DETAILS
6. ASSEMBLY DETAILS
7. STEEL PILE CAP DETAILS
8. STEEL PILE CAP DETAILS
9. BEARING AND ERECTION DETAILS
10. RAILING LAYOUT AND DETAILS
11. RAILING DETAILS
12. RAILPOST DETAILS
- P1. PRECAST PANEL DETAILS
- P2. PRECAST PANEL DETAILS
- G1. PRECAST PRESTRESSED CHANNEL GIRDER DETAILS
- G2. PRECAST PRESTRESSED CHANNEL GIRDER DETAILS
- G3. PRECAST PRESTRESSED CHANNEL GIRDER DETAILS
- G4. PRECAST PRESTRESSED CHANNEL GIRDER DETAILS
- G5. PRECAST PRESTRESSED CHANNEL GIRDER DETAILS

## DESIGN DATA

### SPECIFICATIONS

AASHTO LRFD Bridge Design Specifications, First Edition, 1994 plus 1996/97 Interims

### VEHICULAR LIVE LOADING

1. Modified AASHTO HSS-25 Truck
2. AASHTO LRFD "HL-93" Loading

### STRUCTURAL CONCRETE

CSA A23.1, Exposure Class C-1 Air content category 1

1. PRECAST PRESTRESSED CONCRETE CHANNEL GIRDERS -  $f_c = 45$  MPa at 28 days  
 $f_{ci} = 35$  MPa at time of de-stressing
2. PRECAST PANELS -  $f_c = 35$  MPa

### REINFORCING STEEL

1. PRECAST PRESTRESSED CONCRETE CHANNEL GIRDERS - CAN/CSA-G30.18-M92 Grade 400W black (i.e. no epoxy coating)
2. PRECAST PANELS - CAN/CSA-G30.18-M92 Grade 400W black (i.e. no epoxy coating)

### STRUCTURAL STEEL

1. All Structural Steel shall conform to CAN/CSA G40.21-M92 Grade 300W
2. HSS Tubing for Bridge Rail shall conform to CAN/CSA G40.21-M92 Grade 350W

### PRESTRESSING STRAND

20-13 # low relaxation strands,  $f_{pu} = 1860$  MPa

### PILE LOADING

	END PILE BENTS	INTERMEDIATE PILE BENTS
MAXIMUM FACTORED LOAD	kN	kN
FACTORED BEARING RESISTANCE	kN	kN

## HYDRAULIC DESIGN DATA

### DESIGN DISCHARGE

Q3% - m<sup>3</sup>/sec  
V3% - m/s

## SURVEY CONTROL

HORIZONTAL DATUM: NAD83CSRS

VERTICAL DATUM: CGVD28

ELLIPSOID: GRS 1980

GEOID (HT2.0): -----

UTM: ZONE ----

SCALE FACTOR: -----

### SITE CONTROL POINT DATA

CONTROL POINT #-----	NORTHING: -----	-----
	EASTING: -----	-----
	ELEVATION: -----	-----
	DATE: -----	-----
CONTROL POINT #-----	NORTHING: -----	-----
	EASTING: -----	-----
	ELEVATION: -----	-----
	DATE: -----	-----
CONTROL POINT #-----	NORTHING: -----	-----
	EASTING: -----	-----
	ELEVATION: -----	-----
	DATE: -----	-----

TP. -

RGE. -

## LOCATION MAP

Not to Scale

# MANITOBA INFRASTRUCTURE

WATER MANAGEMENT AND STRUCTURES

RELEASED FOR CONSTRUCTION BY :

EXECUTIVE DIRECTOR OF STRUCTURES

DATE -----



## ENVIRONMENTAL APPROVALS

- MANITOBA ENVIRONMENT ACT LICENCE  
DATE : \_\_\_\_\_  
FILE # : \_\_\_\_\_
- FISHERIES AND OCEANS CANADA - AUTHORIZATION OR REVIEW  
DATE : \_\_\_\_\_  
FILE # : \_\_\_\_\_
- TRANSPORT CANADA - NAVIGATION ACT  
DATE : \_\_\_\_\_  
FILE # : \_\_\_\_\_
- MANITOBA INFRASTRUCTURE ENVIRONMENTAL APPROVAL  
DATE : \_\_\_\_\_  
FILE # : \_\_\_\_\_
- ENVIRONMENTAL REVIEW COMPLETED  
DATE : \_\_\_\_\_  
COMPLETED BY : \_\_\_\_\_

ALL DIMENSIONS ARE IN MILLIMETRES (mm) AND ALL ELEVATIONS AND STATIONS ARE IN METRES (m) UNLESS SHOWN OTHERWISE.

DRAWN BY:

DATE:

SHEET No. 1



CHECKED BY:

DATE:


SITE No.








**UTILITY DISCLAIMER:**  
 LOCATIONS OF UTILITIES AS SHOWN ARE BASED ON READILY AVAILABLE INFORMATION. NO GUARANTEE IS GIVEN THAT ALL UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONTRACTOR SHALL CONFIRM THE EXISTENCE AND LOCATION OF UTILITIES BY OBTAINING FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.



EDGE TREATMENT



OVERLAPPING DETAILS

RIP RAP DETAILS

Not To Scale

- NOTES:
- All geotextile shall be Non-Woven Geotextile, Class I (Heavy Duty) from the Manitoba Infrastructure's Approved Product List.
  - Geotextile shall be placed under all rip rap, overlapping 600mm in direction of flow.

NOTE:  
 Existing pile bents to be removed by Bridge Contractor.

REVISIONS	

SITE AND EROSION CONTROL DETAILS	

DATE	BY	DESCRIPTION

**Manitoba Infrastructure**  
 Water Management and Structures

RELEASED FOR CONSTRUCTION BY: \_\_\_\_\_

EXECUTIVE DIRECTOR OF STRUCTURES DATE


SCALE: 1:200

SHEET No. 4

or as shown SITE No. \_\_\_\_\_


PLACE ENGINEERS ELECTRONIC SEAL HERE






**NOTE:**  
A minimum of 1 - 3 thick x 300 wide elastomeric sheet to be installed on all wingwall and ballast wall piles (field cut length of sheet required for ballast wall piles). Sheets to be bonded to pile or panel with approved adhesive. Additional sheets to be placed as required. Field cut additional sheets to fit if required.


**PART SIDE ELEVATION**  
Bridge railing not shown for clarity



**DETAIL OF LATERAL CONNECTION ANGLE**  
Scale 1:2




**DETAIL "B"**  
Scale 1:10




**SECTION B-B**  
Scale 1:10


- NOTES:**
1. RE-BOLTING
    - a) GIRDER LATERAL CONNECTION
      - Bolts Mk. "R1" - c/w one F436 hardened washer, one structural plate washer Mk. "W1", one pair Nord-Lock washers and one Grade DH heavy hex. nut.
    - b) STEEL CAP
      - Bolts Mk. "R30" - One F436 hardened washer, one hardened bevel washer and one Grade DH heavy hex. nut.
      - Bolts Mk. "R32" - One hardened bevel washer and one Grade DH heavy hex. nut.
      - Bolts Mk. "R35" - Two F436 hardened washers and one Grade DH heavy hex. nut.
    - c) PRECAST PANELS
      - Bolts Mk. "R36" - Two F436 hardened washers and one Grade DH heavy hex. nut.
      - Bolts Mk. "R34" - One F436 hardened washer and one structural plate washer Mk. "A2", no nuts.
      - Threaded rod Mk. "TR2" - One standard flat washer, one structural lock washer, structural plate washer Mk. "A1" and one stainless steel hex. nut.
      - Threaded rod Mk. "TR3" - Two filler plates Mk. "S4", one structural lock washer, two standard flat washers and two hex. nuts, Filler plate Mk. "S5" if required.
    - d) GIRDER TO STEEL CAP
      - Threaded rod Mk. "TR1" - one standard flat washer and structural lock washer and two hex. nuts.
    - e) High strength bolts shall be tightened by the turn-of-nut method as per Bridge Specifications. Ensure nuts are lubricated prior to bolting.
    - f) Fill counter bored holes with mastic filler after tightening bolts.
  2. When grouting dowel holes in girders, ensure that there is no grout between bottom of girder and bearing plate.
  3. Apply galvalloy to all field welds & areas where galvanizing has been damaged.
  4. Impregnated expanding joint sealant shall be installed as per manufacturer's recommendations.



**SECTION AT ABUTMENT**  
Scale 1:10



**DETAILS AT INTERMEDIATE BENT**  
Scale 1:10




**DETAIL "C"**  
Scale 1:1

**NOTE:**  
For location of SECTIONS "B-B" & "DETAIL B" see Sheet No. 6.


REVISIONS		ASSEMBLY DETAILS	
DATE	DESCRIPTION		
		<p><b>Manitoba</b> Infrastructure Water Management and Structures</p>	
		<p>RELEASED FOR CONSTRUCTION BY: _____ DATE: _____</p>	
		<p>EXECUTIVE DIRECTOR OF STRUCTURES</p>	
		<p>SCALE: 1:30 SHEET No. 7</p>	
		<p>or as shown SITE No. _____</p>	

**PLACE ENGINEERS ELECTRONIC SEAL HERE**

DESIGN BY: B.A.N.	EXECUTIVE DIRECTOR OF STRUCTURES	DATE
CHECKED: K.P.	SCALE: 1:30	SHEET No. 7
DETAILS CHECKED:	or as shown	SITE No. _____




ELEVATION  
**STEEL CHANNEL MK "P3"**




PLAN  
**STEEL PLATE MK "P1" & "P1a"**  
Plate Mk. "P1" as shown, Plate "P1a" opposite hand

FOR ABUTMENTS




ELEVATION  
**STEEL CHANNEL MK "P4"**



PLAN  
**STEEL PLATE MK "P2"**


FOR INTERMEDIATE PILE BENTS

REVISIONS		STEEL PILE CAP DETAILS	
DATE	BY	DESCRIPTION	RELEASED FOR CONSTRUCTION BY:
DESIGN SEAL	RECORD SEAL	 Infrastructure Water Management and Structures	
PLACE ENGINEERS ELECTRONIC SEAL HERE		BY: <u>  B.A.N.  </u>	EXECUTIVE DIRECTOR OF STRUCTURES DATE
		CHECKED: <u>                    </u>	SCALE: <u>Scale 1:20</u> SHEET No. <u>  8  </u>
		BY: <u>          K.P.          </u>	or as shown: <u>          </u> SITE No. <u>          </u>
DETAILS	CHECKED: <u>                    </u>		


**BILL OF MISCELLANEOUS METAL 9 600 ROADWAY WIDTH - 3 SPAN - 0 DEGREE SKEW** Site No. \_\_\_\_\_

MARK No.	No.	DESCRIPTION	CORROSION PROTECTION	SIZE	LENGTH	REMARKS	COMPONENT MASS	MASS PER UNIT	TOTAL MASS
P1	2	Steel plate	Hot dip galvanized						1602.85
		Each unit to be fabricated from:							
		1 - Steel plate		PL 32x550	5 800	See detail for Abutment	801.328	801.328	
		8 - Nelson Type NBL, no thread studs		10 dia.	19	Part No. 101-063-167	0.012	0.096	
								801.424	
P1a	2	Steel plate	Hot dip galvanized						1602.85
		Each unit to be fabricated from:							
		1 - Steel plate		PL 32x550	5 800	See detail for Abutment	801.328	801.328	
		8 - Nelson Type NBL, no thread studs		10 dia.	19	Part No. 101-063-167	0.012	0.096	
								801.424	
P2	4	Steel plate	Hot dip galvanized						2713.73
		Each unit to be fabricated from:							
		1 - Steel plate		PL 32x500	5 400	See detail for Intermediate Bent	678.240	678.240	
		16 - Nelson Type NBL, no thread studs		10 dia.	19	Part No. 101-063-167	0.012	0.192	
								678.432	
P3	4	Steel channel	Hot dip galvanized	C310x45	11 600	See detail for Abutment	518.520	2074.08	
P4	4	Steel channel	Hot dip galvanized	C310x45	10 800	See detail for Intermediate Bent	482.760	1931.04	
R30	124	A325 bolt assembly	Hot dip galvanized	16 dia.	89	Steel plate to channels	0.245	30.38	
R32	44	A325 bolt assembly	Hot dip galvanized	16 dia.	76	Steel plate to channels Cbore holes	0.225	9.90	
R35	336	A325 bolt assembly	Hot dip galvanized	22 dia.	64	Channels to piles	0.461	154.90	
R36	48	A325 bolt assembly	Hot dip galvanized	16 dia.	64	Angles Mk. "S1" to piles & bracket Mk. "S2" to cap	0.205	9.84	
S1	20	Angle	Hot dip galvanized	L 152x152x13	250	As detailed	7.250	145.00	
S2	4	Bracket	Hot dip galvanized			As detailed	11.226	44.90	
S3	16	Plate	Hot dip galvanized	PL 6x300		As detailed	3.223	51.57	
S4	32	Filler plate	Hot dip galvanized	PL 6x100	300	As detailed	1.413	45.22	
S5	16	Filler plate	Hot dip galvanized	PL 3x100	300	As detailed	0.707	11.31	
A1	16	Structural plate w/asher	Hot dip galvanized	PL 10x150	150	As detailed - One to threaded rod Mk. "TR2"	1.766	28.26	
A2	8	Structural plate w/asher	Hot dip galvanized	PL 10x90	90	As detailed - One to bolt Mk. "R34"	0.636	5.09	
TR1	48	Threaded rods c/w tw o hex. nuts	Hot dip galvanized	19 dia.	400	Girder to steel cap plate	0.940	45.12	
TR3	32	Threaded rods c/w tw o hex. nuts	Hot dip galvanized	19 dia.	300	Steel plates Mk. "S3" to precast panels	0.660	21.12	
	168	Hardened bevel w/asher	Hot dip galvanized	for 16 dia. bolts		One to bolts Mk. "R30" & "R32"	0.110	18.48	
	16	Standard flat w/asher	Hot dip galvanized	for 13 dia. rod		One to threaded rod Mk. "TR2"	0.010	0.16	
	112	Standard flat w/asher	Hot dip galvanized	for 19 dia. rod		One to "TR1", tw o to "TR3"	0.020	2.24	
	16	Structural lock w/asher	Hot dip galvanized	for 12 dia. rod		One to threaded rod Mk. "TR2"	0.010	0.16	
	80	Structural lock w/asher	Hot dip galvanized	for 19 dia. rod		One to "TR1" & "TR3"	0.020	1.60	
	336	F436 Hardened w/asher	Hot dip galvanized	for 22 dia. bolts		One to bolt Mk. "R35"	0.032	10.75	
	48	F436 Hardened w/asher	Hot dip galvanized	for 16 dia. bolts		One to bolt Mk. "R36"	0.014	0.67	
R1	168	A325 bolt assembly	Hot dip galvanized	22 dia.	76	R.C. girder connection	0.499	83.83	
W1	168	Structural flat w/asher	Hot dip galvanized	for 22 dia. bolts		One to bolt Mk. "R1"	0.050	8.40	
	168	Pair Nord-Lock lock w/ashers		for 22 dia. bolts		One pair to bolt Mk. "R1"	0.020	3.36	
SH1	84	Shim plate	Hot dip galvanized	PL 2.5x80	180	As detailed - use as required	0.231	19.40	
SH2	84	Shim plate	Hot dip galvanized	PL 5x80	180	As detailed - use as required	0.463	38.89	
									<b>TOTAL MASS (kg) = 10715.10</b>


**NOTES:**  
 1. All material noted in the above Bill shall be hot dip galvanized after fabrication in accordance with CSA G164 for a minimum net retention of 610 gm/m<sup>2</sup> unless otherwise stated in the specified material ASTM standards. The fabricator and galvanizer shall safeguard against embrittlement using recommended practices from applicable standards.  
 2. Seal all welds prior to galvanizing.  
 3. Apply Galvaloy to all field welds and areas where galvanizing has been damaged.  
 4. All bolts and threaded rod in the above Bill shall be Imperial thread.





**ANGLE MK. "S1"**




**BRACKET MK. "S2"**




**PLATE MK. "S3"**




**FILLER PLATES MK. "S4" & "S5"**



**WASHER MK. "A1"**




**WASHER MK. "A2"**



**SHIM PLATES MK. "SH1" & "SH2"**

REVISIONS		STEEL PILE CAP DETAILS	
DATE	DESCRIPTION		
		RELEASED FOR CONSTRUCTION BY: _____ EXECUTIVE DIRECTOR OF STRUCTURES DATE: _____	
		SCALE: 1:5 SHEET No. 9 or as shown SITE No. _____	
		DESIGN BY: B.A.N. CHECKED: _____	
		DETAILS BY: K.P. CHECKED: _____	
PLACE ENGINEERS ELECTRONIC SEAL HERE		EXECUTIVE DIRECTOR OF STRUCTURES DATE: _____	





BILL OF BEARINGS			9 600 ROADWAY WIDTH - 3 SPAN	Site No.
No.	LOCATION	DESCRIPTION	REMARKS	
48	SU.1 - SU.4	Elastomeric bearings	As detailed	



**NOTE:**

- Elastomer shall be natural rubber. Elastomer shall be AASHTO low temperature Grade 5 with a minimum shear modulus  $G \geq 0.9$  MPa and a 60 durometer Shore A hardness.
- Internal steel reinforcing plates for laminate bearings shall be rolled mild steel with a minimum yield strength of 300 Mpa.

**PLAN**  
Scale 1:10

**PART CROSS SECTION**  
Scale 1:2

**ELASTOMERIC BEARINGS**




**NOTE :**  
Threaded rods Mk."TR1", set exactly on centreline of holes in precast girders and grouted. Field drill 21 dia. hole in steel plate to match girders.

- NOTES:**
- Re: Girder Erection Operations Behind Abutment Ballast Walls
- Surcharge loading on the backfill resulting from girder erection operations shall be minimized near the precast concrete ballast walls and wingwalls.
  - Where possible, girder erection equipment shall be positioned such that there are no surcharge loads behind the back face of the precast panels within a distance equal to the depth of backfill to the bottom of the panels at the time of girder erection.
  - Should the Contractor propose to encroach on this zone, the following requirements must be satisfied:
    - Submit a girder erection procedure for approval outlining type, configuration, weights and locations of equipment including expected tipping forces on crane outriggers, etc.
    - Perform all precautionary measures outlined by the Department as a result of that submission.
    - All surcharge loads encroaching in this zone must be distributed over an area not less than 2.0 m<sup>2</sup>.

REVISIONS		BEARING AND ERECTION DETAILS	
DATE	DESCRIPTION		
		 Infrastructure Water Management and Structures	RELEASED FOR CONSTRUCTION BY:
			EXECUTIVE DIRECTOR OF STRUCTURES DATE
DESIGN	BY: B.A.N.	SCALE: 1:100	SHEET No. 10
CHECKED:			
DETAILS	BY: K.P.	or as shown	SITE No. 1-1
CHECKED:			

PLACE ENGINEERS ELECTRONIC SEAL HERE



SU.1 SU.2 SU.3 SU.4  
 END SPAN INTERMEDIATE SPAN END SPAN  
 GP2 GP2

RAILS		SLEEVES		RAILPOSTS	
T1	T2	B1	B4	ST2	SB2
2	2	2	2	12	2


RAILS		SLEEVES	
T3	B5	ST1	SB1
2	2	2	2

RAILS		SLEEVES		RAILPOSTS
T1	B1	B3	ST2	SB2
4	2	2	2	14


RAILS		SLEEVES	
T3	B5	ST1	SB1
2	2	2	2

RAILS		SLEEVES		RAILPOSTS	
T1	T2	B1	B4	ST2	SB2
2	2	2	2	12	2


**RAILING LAYOUT**  
 Not to Scale




ELEVATION




SECTION A-A



TYPICAL SECTION




ELEVATION C-C  
 Showing edge screed installation detail




DETAIL "A"  
 Showing edge screed installation detail  
 Scale 1:5

- NOTES:
- All railposts shall be Mk. "GP1" unless noted otherwise.
  - This sheet to be read in conjunction with Sheets & .



SECTION B-B

**APPROACH RAIL CONNECTION DETAILS**



TYPICAL OF CONTINUOUS RAILS

RAIL END CONNECTION

TYPICAL AT PILE BENT

**RAILING ERECTION DETAILS**  
 Scale 1:5


**RAILPOST ERECTION DETAILS**

- NOTES:
- High strength bolts Mk. "R27" & "R28" shall be tightened by turn-of-nut method as per Specification 1061. These bolts to be supplied by the Girder Fabricator. For quantities see Bill of Miscellaneous Metal on Girder sheet.
  - High strength bolted connection may be shimmed to a maximum of 12 mm with shims Mk. "RS3" & "RS4".


REVISIONS		RAILING LAYOUT AND DETAILS	
DATE	BY	DESIGN SEAL	RECORD SEAL
		Water Management and Structures	
DESIGN	BY: _____	RELEASED FOR CONSTRUCTION BY: _____	
CHECKED: _____	SCALE: _____	EXECUTIVE DIRECTOR OF STRUCTURES DATE	
DETAILS	BY: _____	1:10 SHEET No. _____	
CHECKED: _____	or as shown	SITE No. _____	









PLAN




EXTERIOR ELEVATION  
EXTERIOR GIRDER MK. "G1"




PLAN



ELEVATION  
INTERIOR GIRDER MK. "G2"




PLAN



ELEVATION  
GIRDER CONCRETE DETAILS


NOTE: The end of girder will fall between POINT "A" and POINT "C" on curve because of various skew angles.



SECTION A-A  
Typical at both ends of girders  
Scale 1:15

SECTION B-B  
Scale 1:15


END VIEW  
Scale 1:15



ELEVATION

SECTION C-C

DETAIL "A"  
Scale 1:5



ELEVATION


SECTION D-D

DETAIL "B"  
Scale 1:5


NOTES:

- Design in accordance with AASHTO LRFD Bridge Design Specifications, First Edition, 1994 plus 1996/1997 interims.
- Design Vehicular Live Load: Modified AASHTO HSS-25 AASHTO LRFD "HL-93"
- Design distribution factor = 0.5 lanes/girder.
- Concrete strength:  $f_{ci}$  = 35 MPa @ 28 days,  $f_c$  = 45 MPa
- Prestressing steel: 13 mm  $\phi$  low relaxation strands  
Minimum ultimate strength,  $f_{pu}$  = 1860 MPa  
Jacking force/strand,  $f_{pj}$  = 128.5 kN/strand
- Girder dimensioning tolerances: Length 3 mm  $\pm$   
Cross section 2 mm  $\pm$
- Approximate mass per girder = 12 000 kg


REVISIONS		PRECAST PRESTRESSED CHANNEL GIRDER DETAILS	
DATE	BY	DESIGN SEAL	RECORD SEAL
<p>PLACE ENGINEERS ELECTRONIC SEAL HERE</p>		<p><b>Manitoba</b> Infrastructure Water Management and Structures</p>	
		<p>RELEASED FOR CONSTRUCTION BY: _____</p>	
DESIGN		EXECUTIVE DIRECTOR OF STRUCTURES DATE	
CHECKED: _____		SCALE: _____	
DETAILS		SHEET No. G1	
CHECKED: _____		or as shown SITE No. _____	




ELEVATION  
GIRDER STRAND LAYOUT



END VIEW  
Typical layout of 20 - 13 #  
Low Relaxation straight strands





PART PLAN  
Typical at both ends of girders



SECTION E-E  
Scale 1:5

BEARING RECESS DETAILS


REVISIONS		PRECAST PRESTRESSED CHANNEL GIRDER DETAILS	
DATE	DESCRIPTION		
DESIGN	BY: <b>B.A.N.</b>		RELEASED FOR CONSTRUCTION BY: _____
DETAILS	BY: <b>K.P.</b>		EXECUTIVE DIRECTOR OF STRUCTURES DATE
<p style="text-align: center;">PLACE ENGINEERS ELECTRONIC SEAL HERE</p>		SCALE: <b>Scale 1:20</b>	SHEET No. <b>G2</b>
		or as shown	SITE No. <b> </b>



PLAN VIEW

FRONT VIEW


REAR VIEW



SECTION A-A


SECTION B-B

RAILPOST ANCHOR UNIT MK. "U1"



FRONT VIEW


REAR VIEW



SECTION C-C

SECTION D-D


RAILPOST ANCHOR UNIT MK. "U2"




SIDE VIEW

ELEVATION

LATERAL CONNECTION ANGLE MK. "LC1"



PLAN



SECTION E-E  
Scale 1:2


END VIEW  
Scale 1:2

GIRDER END ANGLE MK. "S7"


BILL OF MISCELLANEOUS METAL				for 12 m LONG GIRDERS 9 600 ROADWAY - 3 SPANS		Site No.
MARK No.	No.	DESCRIPTION	CORROSION PROTECTION	SIZE	LENGTH	REMARKS
U1	42	Railpost anchor unit	Hot dip galvanized			
		Each unit is fabricated from:				
		1 - Angle		L152x152x13	250	As detailed
		2 - Heavy hex. nuts		for 22 dia. bolt		Grade DH or 2H
		2 - Studs		19 dia.	150	Headed stud anchors, ASTM A108
		3 - Bars		for 19 dia. Bolt	600	Nelson deformed bar anchors, Type D2L
		2 - Tubes				Metal or plastic capped - As detailed
U2	42	Railpost anchor unit	Hot dip galvanized			
		Each unit is fabricated from:				
		1 - Plate		PL 13x100	250	As detailed
		2 - Heavy hex. nuts		for 19 dia. bolt		Grade DH or 2H
		3 - Studs		10 dia.	100	Headed stud anchors, ASTM A108
		2 - Tubes				Metal or plastic capped - As detailed
LC1	168	Lateral connection angle	Hot dip galvanized			
		Each unit is fabricated from:				
		1 - Angle		L89x64x9.5	300	As detailed
		2 - Studs		19 dia.	200	Headed stud anchors, ASTM A108
		2 - Studs		19 dia.	125	Headed stud anchors, ASTM A108
S7	48	Girder end angle	Hot dip galvanized			
		Each unit is fabricated from:				
		1 - Angle		L76x76x6.4	1 194	As detailed
		2 - Plates		PL 3x75	75	As detailed
		3 - Studs		10 dia.	100	Headed stud anchors, ASTM A108
48		Ferrule loop insert	Stainless steel	for 13 dia. Bolt		Richmond anchor, Type LF-W with mounting washer
TR2	16	Threaded rod	Stainless steel	13 dia.	250	c/w hex. nut
R27	84	A325 bolt c/w F436 hardened washer	Hot dip galvanized	22 dia.	229	Heavy hex. no nut, ASTM F3125
R28	84	A325 bolt c/w F436 hardened washer	Hot dip galvanized	19 dia.	64	Heavy hex. no nut, ASTM F3125

- NOTES:
- All material in the above Bill shall be supplied by the GIRDER CONTRACTOR.
  - All structural steel shall conform to CAN/CSA G40.21-M92 Grade 300W.
  - All material noted in the above Bill shall be hot dip galvanized after fabrication in accordance with CSA G164 for a minimum net retention of 610 g/m<sup>2</sup> unless otherwise stated in the specified material ASTM standards. The fabricator and galvanizer shall safeguard against embrittlement using recommended practices from applicable standards.
  - Seal all welds prior to galvanizing.
  - Grade DH or 2H galvanized nuts for A325 bolts shall be overlapped to a minimum amount required for the fastener assembly in accordance with ASTM F3125. The nuts shall be lubricated with a lubricant containing a visible dye. The lubricant shall be clean and dry to the touch.
  - All bolts and inserts in the above Bill shall be Imperial thread.
  - Stainless steel shall conform to the requirements of ASTM A320, Class B8.


REVISIONS		PRECAST PRESTRESSED CHANNEL GIRDER DETAILS	
DATE	BY	DESIGN SEAL	RECORD SEAL
		PLACE ENGINEERS ELECTRONIC SEAL HERE	
		<b>Manitoba</b> Infrastructure Water Management and Structures	
		RELEASED FOR CONSTRUCTION BY:	
		EXECUTIVE DIRECTOR OF STRUCTURES DATE	
		SCALE: Scale 1:5 SHEET No. G3	
		or as shown SITE No.	




PLAN OF GIRDER




SECTION A-A




SECTION B-B




ELEVATION OF GIRDER



END VIEW C-C



PART SECTION D-D



DETAIL AT RAILPOST ANCHOR

Scale 1:10

NOTES:

1. Concrete cover shall be 25 mm unless noted otherwise.
2. Reinforcing details are typical for all 12 m girders unless noted otherwise.
3. Bar Mark labels with suffix \_G1 are Exterior girders and suffix \_G2 are Interior girders. See Bill of Reinforcing Sheet No. G.

REVISIONS		PRECAST PRESTRESSED CHANNEL GIRDER DETAILS	
DATE	BY	DESCRIPTION	RELEASED FOR CONSTRUCTION BY:
			EXECUTIVE DIRECTOR OF STRUCTURES DATE
			SCALE: SHEET No. <b>G4</b>
			or as shown SITE No. <b>11</b>



PLACE ENGINEERS ELECTRONIC SEAL HERE




BILL OF REINFORCING STEEL - 12 M GIRDERS								SITE No.
MARK	TYPE	PIN DIAMETER	LENGTH	GIRDER TYPE	No. of GIRDERS	No. of BARS PER GIRDER	TOTAL No. of BARS PER GIRDER TYPE	BENDING DIAGRAM
1001_G1	BENT	45	4 080	G1	6	8	48	
1002_G1	BENT	45	3 660	G1	6	10	60	
1003_G1	BENT	45	2 950	G1	6	8	48	
1004_G1	STR		1 000	G1	6	4	24	
1501_G1	BENT	65	2 440	G1	6	41	246	
1502_G1	STR		10 300	G1	6	8	48	
1503_G1	STR		1 100	G1	6	12	72	
1001_G2	BENT	45	4 080	G2	18	8	144	
1002_G2	BENT	45	3 660	G2	18	10	180	
1003_G2	BENT	45	2 950	G2	18	8	144	
1004_G2	STR		1 000	G2	18	4	72	

BILL OF REINFORCING STEEL - 12 M GIRDERS								SITE No.
MARK	TYPE	PIN DIAMETER	LENGTH	GIRDER TYPE	No. of GIRDERS	No. of BARS PER GIRDER	TOTAL No. of BARS PER GIRDER TYPE	BENDING DIAGRAM
1501_G2	BENT	65	2 440	G2	18	41	738	
1502_G2	STR		10 300	G2	18	8	144	
1503_G2	STR		1 100	G2	18	12	216	
Total volume of structural concrete per exterior girder							4.94 m³	
Total volume of structural concrete per interior girder							4.93 m³	
<b>NOTES:</b>								
1. All dimensions given in bending diagram are out to out, except radii and extensions on 90°, 135° & 180° hooks. Extensions on 90°, 135° & 180° hooks are the "A" or "C" dimensions for standard 90°, 135° & 180° hooks referenced from the RSIC "Manual of Standard Practice". Radii are inside dimensions. All reinforcing steel bends and hooks shall conform to Clause 6.6.2 of C.S.A. A23.1-04, unless noted otherwise in the BILL OF REINFORCING STEEL.								
2. All reinforcing steel shall be deformed steel, unless noted otherwise in the BILL OF REINFORCING STEEL.								
3. All reinforcing steel shall conform to CSA G30.18-M92 "Billet Steel Bars for Concrete Reinforcement" Grade 400W, unless noted otherwise in the BILL OF REINFORCING STEEL.								
4. Like bars shall be bundled, securely tied and identified as to Mark and Site No. by appropriate means. All other items to be identified in a similar fashion.								
5. All bars shall be bent in accordance with the following detail:								


REVISIONS		PRECAST PRESTRESSED CHANNEL GIRDER DETAILS	
DATE	BY	DESIGN	DESCRIPTION
		DESIGN SEAL	RECORD SEAL
PLACE ENGINEERS ELECTRONIC SEAL HERE		<b>Manitoba</b> Infrastructure Water Management and Structures	
		RELEASSED FOR CONSTRUCTION BY: _____ DATE _____	
		DESIGN BY: _____ CHECKED: _____	EXECUTIVE DIRECTOR OF STRUCTURES _____ SCALE: _____
		DETAILS BY: _____ CHECKED: _____	SHEET No. <b>65</b> SITE No. _____





**PLAN**

The panel fabricator shall be responsible for the supply and installation of adequate lifting devices



**SECTION A-A  
DETAIL "A"**

BILL OF REINFORCING FOR PRECAST PANELS							SITE No. _____			
MARK	TYPE	PIN DIAMETER	LENGTH	PANEL TYPE	No. of PANELS	No. of BARS PER PANEL	TOTAL No. of BARS PER PANEL TYPE	BENDING DIAGRAM		
1501_N1	STR		5 700	N1	2	6	12			
1502_N1	STR		600	N1	2	20	40			
1501_N1a	STR		5 700	N1a	2	6	12			
1502_N1a	STR		600	N1a	2	20	40			
1501_N2	STR		6 750	N2	2	10	20			
1502_N2	STR		1 200	N2	2	24	48			
1501_N3	STR		4 650	N3	2	10	20			
1502_N3	STR		1 200	N3	2	17	34			
1501_N4	STR		4 900	N4	2	16	32			
1502_N4	STR		1 900	N4	2	17	34			
1501_N4a	STR		4 900	N4a	2	16	32			
1502_N4a	STR		1 900	N4a	2	17	34			
Total mass of reinforcing steel							1497.78	kg		
Panel Type					N1	N1a	N2	N3	N4	N4a
Area m <sup>2</sup> /panel					4.10	4.10	8.90	6.20	10.00	10.00
Total area of precast Panels							86.60	m <sup>2</sup>		

**NOTES:**

- All dimensions given in bending diagram are out to out, except radii and extensions on 90°, 135° & 180° hooks. Extensions on 90°, 135° & 180° hooks are the "A" or "G" dimensions for standard 90°, 135° & 180° hooks referenced from the RSIC "Manual of Standard Practice". Radii are inside dimensions. All reinforcing steel bends and hooks shall conform to Clause 6.6.2 of C.S.A. A23.1-04, unless noted otherwise in the BILL OF REINFORCING STEEL.
- All reinforcing steel shall be deformed steel, unless noted otherwise in the BILL OF REINFORCING STEEL.
- All reinforcing steel shall conform to CSA G30.18-M92 "Billet Steel Bars for Concrete Reinforcement" Grade 400W, unless noted otherwise in the BILL OF REINFORCING STEEL.
- Like bars shall be bundled, securely tied and identified as to Mark and Site No. by appropriate means. All other items to be identified in a similar fashion.
- All bars shall be bent in accordance with the following detail:

BILL OF MISCELLANEOUS METAL for PRECAST PANELS						Site No. _____
MARK No.	No.	DESCRIPTION	CORROSION PROTECTION	SIZE	LENGTH	REMARKS
Q5	4	Insert units	Hot dip galvanized			
		Each unit is fabricated from:				
		Steel plate		PL 10 x 150	250	As detailed
		2 - Studs Mk. "A1"		13 dia.	75	Nelson headed concrete anchors, Type H4L, Part No. 101-053-002 - As detailed
		3 - Bars Mk. "A2"		10 dia.	300	Nelson deformed bar anchors, Type D2L, Part No. 101-064-537 - As detailed
		2 - Heavy hex. nuts		for 19 dia. bolt		Grade DH or 2H heavy hex. nut, c/w metal or plastic sleeve
R34	8	A325 bolt c/w F436 hardened w washer		19 dia.	60	

**NOTES:**

- All material noted in the above Bill shall be hot dip galvanized after fabrication in accordance with CSA G164 for a minimum net retention of 610 g/m<sup>2</sup> unless otherwise stated in the specified material ASTM standards. The fabricator and galvanizer shall safeguard against embrittlement using recommended practices from applicable standards.
- Seal all welds prior to galvanizing.
- All structural steel to be CSA G40.21 Grade 300W.
- All bolts and inserts in the above Bill shall be Imperial thread.

**INSERT Mk. "Q5"**  
Scale 1:5

- NOTES:**
- For location of DETAIL "A" see sheet No. P1.
  - Precast panel concrete strength: f'c = 35 MPa.

REVISIONS		PRECAST PANEL DETAILS																	
		 <b>Manitoba</b> Infrastructure Water Management and Structures																	
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 50%;">DATE</td> <td style="width: 50%;">BY</td> </tr> <tr> <td>DESIGN SEAL</td> <td>RECORD SEAL</td> </tr> </table>	DATE	BY	DESIGN SEAL	RECORD SEAL		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td colspan="2">RELEASED FOR CONSTRUCTION BY:</td> </tr> <tr> <td>EXECUTIVE DIRECTOR OF STRUCTURES</td> <td>DATE</td> </tr> </table>	RELEASED FOR CONSTRUCTION BY:		EXECUTIVE DIRECTOR OF STRUCTURES	DATE									
DATE	BY																		
DESIGN SEAL	RECORD SEAL																		
RELEASED FOR CONSTRUCTION BY:																			
EXECUTIVE DIRECTOR OF STRUCTURES	DATE																		
<p><b>PLACE ENGINEERS ELECTRONIC SEAL HERE</b></p>		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td>DESIGN</td> <td>BY: _____ B.A.N./_____</td> <td>SCALE:</td> <td>1 : 2</td> </tr> <tr> <td>CHECKED: _____</td> <td></td> <td>SHEET No. _____</td> <td>P2</td> </tr> <tr> <td>DETAILS</td> <td>BY: _____</td> <td>or as shown</td> <td>SITE No. _____</td> </tr> <tr> <td>CHECKED: _____</td> <td></td> <td></td> <td></td> </tr> </table>	DESIGN	BY: _____ B.A.N./_____	SCALE:	1 : 2	CHECKED: _____		SHEET No. _____	P2	DETAILS	BY: _____	or as shown	SITE No. _____	CHECKED: _____				
DESIGN	BY: _____ B.A.N./_____	SCALE:	1 : 2																
CHECKED: _____		SHEET No. _____	P2																
DETAILS	BY: _____	or as shown	SITE No. _____																
CHECKED: _____																			