



PLAN





Re: Girder Erection Operations Behind Abutment Ballast Walls

- Surcharge loading on the backfill resulting from girder erection operations shall be minimized near the precast concrete ballast walls and wingwalls.
- Where possible, girder erection equipment shall be positioned such that there are no surcharge loads behind the back face of the precast panels within a distance equal to the depth of backfill to the bottom of the panels at the time of girder erection.
- Should the Contractor propose to encroach on this zone, the following requirements must be satisfied:

 Submit a girder erection procedure for approval outlining type, configuration, weights and locations of equipment including expected tipping forces on crane outriggers, etc.
 Perform all precautionary measures outlined by the Department as a result of that submission.
 All surcharge loads encroaching in this zone must be distributed over an area not less than 2.0 m².
- **REVISIONS** BEARING AND ERECTION DETAILS

				_					
DATE	BY	D	ESCRIPTION	†				APPROVED BY:	
DESIGN SEAL			RECORD SEAL	3009 3250	Infrastructure Water Management and Structures			Original signed by Micheal Hagos July 28, 20202 DIRECTOR OF STRUCTURES	
Original signed and sealed by				DESIGN	BY:	A.H.P	DATE	DATE	
Andy Pankratz July 20, 2020				DESIGN	CHECKED:	<u>A.H.P.</u>	SCALE:		
_	, -,			DETAILO	BY:	K.P./N.J.	1:100	SHEET No	
				DETAILS		AUD]h	DDCC DD 0.6 12m ID	

or as shown STD No.PPCC_PR_9.6_12m_IB_BE03